Docker **ASSIGNMENT**



Name – Maithely Sharma
College – University of Petroleum and Energy Studies
EmployeeID – 4057

- 1. Set the base image to Ubuntu
 - o Add File Author / Maintainer
 - Install Nginx
 - o Install necessary tools: vim wget curl net-tools
 - Remove the default Nginx configuration file
 - Copy a configuration file from the current directory
 - Expose ports (80)
 - o Set the default command to execute Nginx when creating a new container

Create a Dockerfile in /etc/docker/bootcamp

```
maithely@maithely: /etc/docker/bootcamp

File Edit View Search Terminal Help

EROM ubuntu

LABEL maintainer="Maithely"

Run apt-get update -y && apt-get install -y \
nginx \
vim \
wget \
curl \
net-tools

RUN rm /etc/nginx/nginx.conf

COPY nginx.conf /etc/nginx/

CMD ["nginx","-g","daemom off;"]
```

Also create a nginx.conf file in bootcamp folder

```
maithely@maithely:/etc/docker/bootcamp$ ls
Dockerfile nginx.conf
maithely@maithely:/etc/docker/bootcamp$ cat nginx.conf
worker_processes 5; ## Default: 1
error log logs/error.log;
pid
          logs/nginx.pid;
worker rlimit nofile 8192;
events {
 worker connections 4096; ## Default: 1024
http {
  include
            conf/mime.types;
  include
           /etc/nginx/proxy.conf;
  include
            /etc/nginx/fastcgi.conf;
  index
          index.html index.htm index.php;
  default type application/octet-stream;
  log_format main '$remote_addr - $remote_user [$time_local] $status '
    "$request" $body_bytes_sent "$http_referer"
    '"$http_user_agent" "$http_x_forwarded for"';
  access log
             logs/access.log main;
  sendfile
               on;
  tcp nopush
  server names hash bucket size 128; # this seems to be required for some vhosts
  server { # php/fastcgi
    listen
                80;
    server name domain1.com www.domain1.com;
    access log logs/domain1.access.log main;
    root
                html;
    location ~ \.php$ {
      fastcgi pass 127.0.0.1:1025;
```

```
maithely@maithely:/etc/docker/bootcamp$ docker build -t nginx .
Sending build context to Docker daemon 4.608kB
Step 1/6 : FROM ubuntu
---> 72300a873c2c
Step 2/6 : LABEL maintainer="Maithely"
---> Using cache
 ---> a62a67271554
Step 3/6 : Run apt-get update -y && apt-get install -y nginx vim wget curl net-tools
---> Using cache
 ---> 41cb710bb72b
Step 4/6 : RUN rm /etc/nginx/nginx.conf
---> Using cache
 ---> 996582433e4c
Step 5/6 : COPY nginx.conf /etc/nginx/
---> e32ecbe2326b
Step 6/6 : CMD ["nginx","-g","daemom off;"]
---> Running in ea896abff04e
Removing intermediate container ea896abff04e
---> 62e361af0aff
Successfully built 62e361af0aff
Successfully tagged nginx:latest
```

maithely@maithely:/etc/docker/bootcamp\$ docker images						
REPOSITORY	TAG	IMAGE ID	CREATED	SIZE		
nginx	latest	62e361af0aff	6 seconds ago	216MB		
ubuntu	latest	72300a873c2c	12 days ago	64.2MB		
hello-world	latest	fce289e99eb9	14 months ago	1.84kB		

2. What is the difference between 'RUN', 'CMD', & 'ENTRYPOINT' in dockerfile?

RUN

- executes the command(s) that you give in a new layer and creates a new image.
- This is mainly used for installing a new package.

CMD

- is the default command to be run by the entrypoint.
- It sets default command and/or parameters, however, we can overwrite those commands or pass in and bypass the default parameters from the command line when docker runs

ENTRYPOINT

- is the program to run the given command.
- It is used when you want to run a container as an executable.
- 3. How to connect docker client to docker daemon running on other host?

For reference : https://nickjanetakis.com/blog/docker-tip-73-connecting-to-a-remote-docker-daemon

Create an ubuntu instance and install docker on it

```
ubuntu@ip-172-31-225-82:~$ sudo apt install docker-ce
Reading package lists... Done
Building dependency tree
Reading state information... Done
The following additional packages will be installed:
  aufs-tools cgroupfs-mount containerd.io docker-ce-cli libltdl7 p
The following NEW packages will be installed:
  aufs-tools cgroupfs-mount containerd.io docker-ce docker-ce-cli
0 upgraded, 7 newly installed, 0 to remove and 53 not upgraded.
Need to get 85.8 MB of archives.
After this operation, 385 MB of additional disk space will be used
Do you want to continue? [Y/n] y
Get:1 http://us-east-1.ec2.archive.ubuntu.com/ubuntu bionic/univers
Get:2 http://us-east-1.ec2.archive.ubuntu.com/ubuntu bionic/univers
Get:3 http://us-east-1.ec2.archive.ubuntu.com/ubuntu bionic/univer
Get:4 https://download.docker.com/linux/ubuntu bionic/stable amd64
Get:5 http://us-east-1.ec2.archive.ubuntu.com/ubuntu bionic/main a
Get:6 https://download.docker.com/linux/ubuntu bionic/stable amd64
Get:7 https://download.docker.com/linux/ubuntu bionic/stable amd64
Fetched 85.8 MB in 2s (51.0 MB/s)
Selecting previously unselected package pigz.
(Reading database ... 56558 files and directories currently instal
Preparing to unpack .../0-pigz_2.4-1_amd64.deb ...
Unpacking pigz (2.4-1) ...
Selecting previously unselected package aufs-tools.
Preparing to uppack .../1-aufs-tools 1%3a4.9+20170918-1ubuntu1 amdu
```

Configure the Docker daemon in the VM to allow remote connections

```
# These commands get run inside of your VM.

# Create the directory to store the configuration file.
sudo mkdir -p /etc/systemd/system/docker.service.d


# Create a new file to store the daemon options.
sudo nano /etc/systemd/system/docker.service.d/options.conf

# Now make it look like this and save the file when you're done:
[Service]
ExecStart=
ExecStart=/usr/bin/dockerd -H unix:// -H tcp://0.0.0.0:2375

# Reload the systemd daemon.
sudo systemctl daemon-reload

# Restart Docker.
sudo systemctl restart docker
```

In the inbound add the port



From local machine

```
maithely@maithely:~/Downloads$ DOCKER_HOST=tcp://54.88.132.185:2375 docker info
Client:
Debug Mode: false
Server:
Containers: 0
  Running: 0
 Paused: 0
 Stopped: 0
 Images: 0
 Server Version: 19.03.7
 Storage Driver: overlay2
 Backing Filesystem: <unknown>
  Supports d_type: true
 Native Overlay Diff: true
 Logging Driver: json-file
Cgroup Driver: cgroupfs
 Plugins:
  Volume: local
  Network: bridge host ipvlan macvlan null overlay
```